

TAPPING NOTES:

- DISTRICT PERSONNEL WILL TAP MAINS FOR DEVELOPMENTS SMALLER THAN 4 LOTS.
- EXCAVATION FOR TAPS, CONTRACTOR SHALL PROVIDE
 A MINIMUM OPENING OF 4 FEET PARALLEL TO THE MAIN
 AND 6 FEET PERPENDICULAR TO THE MAIN (4 FEET ON
 ONE SIDE OF THE MAIN AND 2 FEET ON THE OTHER).
- ALL TAPS ON PVC WATER MAINS REQUIRE PRIOR INSTALLATION OF TAPPING SADDLES.
- 3. A HAND HELD DRILL CANNOT BE USED ON PVC PIPE. ONLY A MANUALLY OPERATED CUTTING TOOL WILL BE ALLOWED.
- 4. PVC TAPS MUST BE MADE ACCORDING TO THE UNI-BELL TAPPING GUIDE FOR PVC PRESSURE PIPE.
- NO TRENCH SHALL BE BACKFILLED UNTIL THE ENTIRE SERVICE LINE HAS BEEN INSPECTED AND APPROVED BY DISTRICT.
- TAP FESS MUST BE PAID PRIOR TO CONNECTION OF SERVICE LINE TO DISTRICT MAIN.

CONTRACTOR SUPPLIED MATERIALS:	
ITEM	MATERIALS
CURB STOP	MUELLER (B25209), FORD BALL (TYPE B44-333-Q) OR EQUAL
SERVICE LINE	TYPE "K" COPPER (CONTINUOUS, NO FITTINGS)
CURB BOX	TYLER SERIES 6500 W/ ADJUSTABLE SERVICE BOX (#94E)
METER PIT	CEMENT 2' DIAMETER X 4' DEEP
METER PIT COVER	20" FLAT CAST IRON DOME W/ 2" PREDRILLED HOLE FOR METER POD AND INNER FROST SHIELD
BEDDING MATERIAL	WASHED SAND OR SQUEEGEE MATERIAL
TRACER WIRE	12 GAUGE STRANDED COPPER TRACER WIRE IF INSTALLING A SERVICE LINE MADE OF UNDETECTABLE MATERIAL.
1½" AND LARGER SERVICE	CONTRACTOR SHALL SUPPLY METER YOKES AND FITTINGS FOR 1 ½" AND LARGER SERVICES.

DISTRICT SUPPLIED MATERIALS:	
3/4" AND 1" TAPS	
CORPORATION STOP	
YOKE/METER	
INSULATOR	
SADDLE ON PVC MAINS	

GENERAL NOTES:

- UTILITY PERMIT IS REQUIRED PRIOR TO COMMENCEMENT OF SERVICE LINE INSTALLATION.
- A \$250 FINE WILL BE ASSESSED IF THE DISTRICT IS UNABLE TO SET A METER DUE TO METER PIT ASSEMBLY DAMAGE, YOKE IMPROPERLY INSTALLED OR ANY OTHER REASON THAT PREVENTS THE PROPER INSTALLATION OF A METER. THE METER WILL NOT BE SET UNTIL FINES ARE PAID AND PROPER REPAIRS ARE MADE.
- 3. WATER SERVICE LOCATIONS SHALL BE PERMANENTLY MARKED ON THE FACE OF THE CURB WITH A "W" STAMPED IN WET CONCRETE.
- 4. METER PITS ARE NOT ALLOWED IN DRIVEWAYS OR CONCRETE.
- SERVICE LINE BEDDING MATERIAL SHALL BE INSTALLED A MINIMIUM 6" BELOW TO A MINIMIUM OF 6" OVER SERVICE. THE BEDDING MATERIAL SHALL EXTEND THE ENTIRE LENGTH OF THE SERVICE LINE.
- 12 GAUGE, STRANDED COPPER TRACER WIRE MUST BE INSTALLED ON SERVICE LINES MADE OF UNDETECTABLE MATERIAL.
- 7. USE OF A SPACE BAR IS **PROHIBITED**, IF ONE IS USED CONTRACTOR WILL BE **FINED** \$250 FOR THE FIRST OFFENSE.
- 8. SOIL AMENDMENT SPECIFICATIONS ARE APPLICABLE FOR DEVELOPMENTS LARGER THAN 2 LOTS. METER WILL NOT BE SET UNTIL SPECS ARE MET.
- DEVELOPMENTS THAT HAVE A COMMON AREA ABOVE 0.75
 ACRES, THE LANDSCAPE AND IRRIGATION SPECIFICATIONS
 ARE APPLICABLE. METER WILL NOT BE SET UNTIL SPECS
 ARE MET.
- 10. 24 HOURS NOTICE IS REQUIRED FOR TAPS, INSPECTIONS AND METER SETS.
- 11. FOR ALL SERVICE LINE STUB-INS:
- 11.1. EXTEND INTO THE PROPERTY A MINIMUM TEN (10) FEET.
- 11.2. MUST INSTALL CURB STOP WITH CURB BOX AND EXTEND SERVICE LINE 5 FEET BEYOND CURB BOX, BRING COPPER PIPE TO GRADE AND TAPE END. MARK END OF STUB OUT WITH A BLUE STEEL TEE POST.
- 11.3. METER PITS ARE NOT ALLOWED UNTIL TAP FEES ARE PAID.

