

TAPPING NOTES:

1. CONTRACTOR RESPONSIBLE FOR MAKING ALL TAPS.
2. TAPS MUST BE MADE IN THE PRESENCE OF AN NTM INSPECTOR.
 - 2.1. SCHEDULE TAPS A MINIMUM OF 24 TO 48 HOURS IN ADVANCE.
3. ALL TAPS ON PVC WATER MAINS REQUIRE PRIOR INSTALLATION OF TAPPING SADDLES.
4. A HAND HELD DRILL CANNOT BE USED ON PVC PIPE. ONLY A MANUALLY OPERATED CUTTING TOOL WILL BE ALLOWED.
5. PVC TAPS MUST BE MADE ACCORDING TO THE UNI-BELL TAPPING GUIDE FOR PVC PRESSURE PIPE.
6. NO TRENCH SHALL BE BACKFILLED UNTIL THE ENTIRE SERVICE LINE HAS BEEN INSPECTED AND APPROVED BY DISTRICT.


MAY UPSIZE SERVICE LINE OR USE DIFFERENT PIPE MATERIAL MIN. 5' OUTSIDE OF METER PIT. 12 GAUGE STRANDED COPPER TRACER WIRE MUST BE INSTALLED IF SERVICE LINE IS MADE OF UNDETECTABLE MATERIAL

GENERAL NOTES:

1. UTILITY PERMIT IS REQUIRED PRIOR TO COMMENCEMENT OF SERVICE LINE INSTALLATION.
2. A \$250 FINE WILL BE ASSESSED IF THE DISTRICT IS UNABLE TO SET A METER DUE TO METER PIT ASSEMBLY DAMAGE, YOKE IMPROPERLY INSTALLED OR ANY OTHER REASON THAT PREVENTS THE PROPER INSTALLATION OF A METER. THE METER WILL NOT BE SET UNTIL FINES ARE PAID AND PROPER REPAIRS ARE MADE.
3. WATER SERVICE LOCATIONS SHALL BE PERMANENTLY MARKED ON THE FACE OF THE CURB WITH A "W" STAMPED IN WET CONCRETE.
4. METER PITS ARE NOT ALLOWED IN DRIVEWAYS OR CONCRETE.
5. SERVICE LINE BEDDING MATERIAL SHALL BE INSTALLED A MINIMUM 6" BELOW TO A MINIMUM OF 6" OVER SERVICE. THE BEDDING MATERIAL SHALL EXTEND THE ENTIRE LENGTH OF THE SERVICE LINE.
6. 12 GAUGE, STRANDED COPPER TRACER WIRE MUST BE INSTALLED ON SERVICE LINES MADE OF UNDETECTABLE MATERIAL.
7. USE OF A SPACE BAR IS **PROHIBITED**, IF ONE IS USED CONTRACTOR WILL BE **FINED** \$250 FOR THE FIRST OFFENSE.
8. SOIL AMENDMENT SPECIFICATIONS ARE APPLICABLE FOR DEVELOPMENTS LARGER THAN 2 LOTS. METER WILL NOT BE SET UNTIL SPECS ARE MET.
9. DEVELOPMENTS THAT HAVE A COMMON AREA ABOVE 0.75 ACRES, THE LANDSCAPE AND IRRIGATION SPECIFICATIONS ARE APPLICABLE. METER WILL NOT BE SET UNTIL SPECS ARE MET.
10. A MINIMUM OF 24 TO 48 HOURS NOTICE IS REQUIRED FOR TAPS, INSPECTIONS AND METER SETS.
11. FOR ALL SERVICE LINE STUB-INS:
 - 11.1. EXTEND INTO THE PROPERTY A MINIMUM TEN (10) FEET.
 - 11.2. MUST INSTALL CURB STOP WITH CURB BOX AND EXTEND SERVICE LINE 5 FEET BEYOND CURB BOX, BRING COPPER PIPE TO GRADE AND TAPE END. MARK END OF STUB OUT WITH A BLUE STEEL TEE POST.
 - 11.3. METER PITS ARE NOT ALLOWED UNTIL TAP FEES ARE PAID.

CONTRACTOR SUPPLIED MATERIALS:	
ITEM	MATERIALS
CURB STOP	MUELLER (B25209), FORD BALL (TYPE B44-333-Q) OR EQUAL
SERVICE LINE	TYPE "K" COPPER (CONTINUOUS, NO FITTINGS)
CURB BOX	TYLER SERIES 6500 W/ ADJUSTABLE SERVICE BOX (#94E)
METER PIT	CEMENT 2' DIAMETER X 4' DEEP
METER PIT COVER	20" FLAT CAST IRON DOME W/ 2" PREDRILLED HOLE FOR METER POD AND INNER FROST SHIELD
BEDDING MATERIAL	WASHED SAND OR SQUEEGEE MATERIAL
1 1/2" AND LARGER SERVICE	CONTRACTOR SHALL SUPPLY METER YOKES AND FITTINGS FOR 1 1/2" AND LARGER SERVICES.

DISTRICT SUPPLIED MATERIALS:	
CORPORATION STOP	
YOKE/METER	
INSULATOR	
SADDLE ON PVC MAINS	

REV. DATE:	07/2020	3/4" AND 1" WATER SERVICE LINE
SCALE:	N.T.S.	
		DWG. NO. W6
NORTH TABLE MOUNTAIN WATER AND SANITATION DISTRICT 14806 WEST 52ND AVENUE GOLDEN, COLORADO 80403-1228		